



SECTION

NOTE:

- 1 USE MODERATELY STIFF MIX OF NON SHRINK CEMENT, SAND AND 1/2" AND LESS DIAMETER GRAVEL WITH 28 DAYS, STRENGTH AT 3,000 P.S.I.
- 2 MIX IS TO BE FORCED INTO ALL GROOVES AND UNDER FLANGE OF FRAME AND LEFT AT OR ABOVE TOP OF FLANGE.
- 3 MAX. OF 4 BRICK OR CONCRETE BLOCKS TO BE USED FOR GRADE CONTROL.
- 4 DO NOT BACKFILL AROUND FRAME AND COVER, FOR 48 HOURS AFTER CON. IS PLACED. THE USE OF HIGH STRENGTH CONCRETE WOULD REDUCE TIME TO (24HRS).
- 5 RESTRICT TRAFFIC LOAD FOR MIN. 24 HOURS.

REVISIONS				INSTALLATION DETAIL FOR ALL FRAMES AND COVERS	DRAWING
NO.	DATE				W-16
ORIGINAL	12/01/06				